


DATUM WGS-1984

SHOLAPUR AIRPORT LATITUDE: 17°37' 39.55"N LONGITUDE: 075°56' 2.54"E ARP ELEVATION: 480.88 M AERO ELEVATION: 483.11 M RWY 15/33: 2009M x 45M	RWY END CO ORDINATES RWY 15 17°38' 8.48"N 075°55' 44.84"E RWY 33 17°37' 14.93"N 075°56' 23.95"E	LIST OF NAV AIDS AT SHOLAPUR AIRPORT S.NO. NAV AIDS CO ORDINATES TOP ELEVATIONS 1. NDB 17°37' 32.866"N 075°55' 55.403"E 478.2 M	SCALE 1:50000 0 1,000 2,000 3,000 4,000 5,000 6,000 7,000 Meters 1. ALL GEOGRAPHICAL COORDINATES ARE IN WGS-1984. 2. ALL ELEVATIONS, CONTOURS AND DIMENSIONS ARE IN METERS.	N ANNUAL RATE OF CHANGE 2"E	COLOR CODED ZONING MAP (GRID FORMAT) OF SHOLAPUR AIRPORT
---	--	--	---	--------------------------------	---



COLOUR LEGEND

 NOC TO BE OBTAINED FROM AAI	 PERMISSIBLE TOP ELEV. 593M AMSL OR BELOW
 PERMISSIBLE TOP ELEV. 513M AMSL OR BELOW	 PERMISSIBLE TOP ELEV. 623M AMSL OR BELOW
 PERMISSIBLE TOPELEV. 523M AMSL OR BELOW	
 PERMISSIBLE TOPELEV. 533M AMSL OR BELOW	
 PERMISSIBLE TOP ELEV. 553M AMSL OR BELOW	

NOTES:-

- THIS CCZM HAS BEEN ISSUED IN ACCORDANCE WITH MoCA NOTIFICATION NO GSR 751(E) RULE 6 IN RESPECT OF SHOLAPUR AIRPORT AND DOES NOT INCLUDE JURISDICTION OF DEFENCE AIRPORT.
- NOC IS NOT REQUIRED FROM AAI FOR BUILDINGS / STRUCTURES PROPOSED TO BE CONSTRUCTED UP TO THE HEIGHT PERMITTED VIDE THIS CCZM. REFER G 751 (E) RULE 7 (2) (3) & (4).
- THE ELEVATION PERMITTED BY CCZM ARE INDICATED ABOVE MEAN SEA LEVEL i.e. AMSL. BUILDING HEIGHT PERMITTED i.e. ABOVE GROUND LEVEL (AGL) WILL BE CALCULATED AS
BUILDING HEIGHT (AGL) = CCZM ELEVATION FOR THE RESPECTIVE GRID - SITE ELEVATION OF THE BUILDING.
- AS PER GSR 751 (E) RULE 4 (4), THE LEVEL ROADS AND LEVEL RAILWAY LINES WITHIN ONE KILOMETER OF THE AIRPORT BOUNDARY WALL SHALL ALSO BE SUBJECT TO ISSUANCE OF THE NO OBJECTION CERTIFICATE.
- AS PER GSR 751 (E) SCHEDULE - 1 (1.2), INSTALLATION OF EXTRA HIGH TENSION HIGH TENSION LINES SHALL NOT BE PERMITTED WITHIN 1500 METERS OF THE INNER EDGE OF THE APPROACH AND TAKE-OFF CLIMB SURFACE.

APPLICABLE FROM DATE: 19-12-2018
(SUBJECT TO REVIEW AND WHEN REQUIRED)

VERSION: 1.0	DATE: 19-12-2018
COMPILED BY: (SR.SUPDT)	(SHARDA KHANNA)
RECOMMENDED BY: AGM (NOC)	(K.K.SONI)
APPROVED BY: GM(NOC)	(R.K.SINGLA)